An Equal Opportunity Employer

Hapchuk, Inc.

226 Rankin Road, Washington, Pa. 15301

Phone: 724-222-6080 Fax: 724-229-7034

Home Improvement Contractor Registration Number PA015030

September 16, 2025

Re: Septic Tank Replacement
1746 PA-980
Canonsburg, PA 15317

Hapchuk, Inc. is equipped and able to replace the septic tank at the property located at 1746 PA-980. The existing septic tanks will be dug up and removed. A new 1,500 gallon dual compartment poly-plastic (Norwesco brand) septic tank will be installed in the in the same location of the existing septic tanks. The new tank will have risers to grade with plastic child safe lids to facilitate future access to the tank. The inlet of the tank will be connected to the existing inlet line and the outlet line of the septic tank will be connected to the existing outlet line exiting the second septic tank. The outlet will be equipped with a Polylok PL-122 effluent filter. The tank will be set on roughly 4" of 2b crushed limestone and will be backfilled on all sides and above with 2b crushed limestone and then topped off to grade with soil from the site. All pipe and fittings used will be pvc schedule 40 and fernco fittings. The price for the above described work and materials will be $13,305.00 (thirteen thousand three hundred five dollars). A permit is required from the Washington County Sewage Council in order to complete this work. You are responsible for obtaining this permit prior to the work taking place. **It is important to understand that replacing the septic tank will not change/benefit the function of any downstream component (i.e. the existing absorption area) located beyond the existing septic tank.**

PA One Call will be used to mark for all public utilities that are in the work area. Hapchuk, Inc. is not responsible for damage to private utilities not marked within 18" on the surface of the ground. Due to the size and weight of our equipment, some disruption to the turf and possibly the driveway is unavoidable. All backfill will be to rough grade only. It is possible that some vegetation (branches/tree limbs) may need to be trimmed or cut in order to gain access to the work site. Our ability to perform this work is highly dependent on the weather and scheduling will be at our sole discretion.

Terms: The price quoted in this proposal will be valid for 60 days from the date of the proposal. A rock clause is in effect. Anything in addition to the above described work and materials will be billed accordingly.

If you have any questions or need more information concerning this proposal, please feel free to call at 724-222-6080.

Sincerely,

Ryan M Allinder

Ryan M. Allinder

Please sign, date and return 1 copy back to us:

SIGN: Mike DeBold

DATE: 9/16/25

50% down payment of $6,652.50 is required before the work can be scheduled. The balance is due at the time the work is completed.