

**ROOF PLAN**



**ROOFING NOTES**

ASPHALT SHINGLES SHALL BE FASTENED TO SOLIDLY SHEATHED DECKS.

ASPHALT SHINGLES SHALL BE ONLY BE USED ON ROOF SLOPES OF 2:12 OR GREATER. FOR ROOF SLOPES FROM 2:12 UP TO 4:12 DOUBLE UNDERLAYMENT APPLICATION IS REQUIRED AS PER R905.2.7.

ASPHALT SHINGLES SHALL HAVE SELF-SEAL STRIPS OR BE INTERLOCKING AND COMPLY WITH ASTM D 225 OR D 3462.


ASPHALT SHINGLES SHALL HAVE THE MINIMUM NUMBER OF FASTENERS REQUIRED BY THE MANUFACTURER. FASTENERS SHALL BE GALVANIZED STEEL, STAINLESS STEEL, ALUMINUM OR COPPER ROOFING NAILS OF A LENGTH TO PENETRATE THROUGH THE ROOFING MATERIALS AND A MINIMUM OF 3/4 INCH INTO THE ROOF SHEATHING. IF THE ROOF SHEATHING IS LESS THAN 3/4 INCH THICK THE FASTENERS SHALL PENETRATE THROUGH THE SHEATHING. FASTENERS SHALL COMPLY WITH ASTM F 1667.

UNDERLAYMENT SHALL BE NO.15 ASPHALT ROOF FELT AND SHALL CONFORM TO ASTM D 226 TYPE I, ASTM D 4869 TYPE I OR ASTM D 6757.

ICE & WATER SHIELD SHALL BE INSTALLED FROM THE LOWEST EDGES OF ALL ROOF SURFACES TO A POINT NO LESS THAN 24 INCHES INSIDE THE EXTERIOR WALL LINE OF THE BUILDING.


CORROSION-RESISTANT METAL FLASHING SHALL BE INSTALLED AT ALL ROOF INTERSECTIONS IN ACCORDANCE WITH MANUFACTURER'S INSTALLATION INSTRUCTIONS.

A CRICKET OR SADDLE SHALL BE INSTALLED ON THE RIDGE SIDE OF ANY CHIMNEY OR PENETRATION MORE THAN 30 INCHES WIDE AS MEASURED PERPENDICULAR TO THE ROOF SLOPE.



**1/A-5**

SCALE: 3/4" = 1'-0"



**2/A-5**

SCALE: 3/4" = 1'-0"

**ROTHE ENGINEERING, P.C.**

641 RT. 212 SAUGERTIES, NY 12477 PHONE: (845)246-6600 FAX: (845)246-6909

NEW RESIDENCE  
ON LANDS OF FLIPPIN CRAZY  
TOWN OF SAUGERTIES, COUNTY OF ULSTER



SCALE : AS NOTED

MODIFIED: 11/4/20

SHEET 5 OF 10